

TECHNICAL SPECIFICATION

Signage & Interactive Flat Panel (IFP) Solution

Digital Signage, Interactive Displays & Video Wall Collaboration System — Etihad Rail HQ, Abu Dhabi | Floors 6, 8 & 9

3

FLOORS COVERED

20+

DISPLAYS DEPLOYED

1

VIDEO WALL SYSTEM

3 YR

WARRANTY

OVERVIEW

Executive Summary

This document presents the technical specification for the supply, installation and configuration of an integrated Digital Signage and Interactive Flat Panel (IFP) solution across **Floors 6, 8 and 9** of the Etihad Rail facility, Abu Dhabi. The solution combines a video-wall array of signage and interactive displays, a collaboration and conferencing bar, wireless content sharing, and an expandable network of interactive panels and professional displays — enabling unified content management, live dashboarding and collaborative meeting capability across multiple floors.

8FLOOR 6 · VIDEO WALL
PANELS**10**FLOOR 8 ·
INTERACTIVE PANELS**6**FLOOR 9 · PRO
DISPLAYS (OPT.)**8×8**HDMI VIDEO WALL
CONTROL

Video Wall Display

DigiBird 8×HDMI-in / 8×HDMI-out video wall controller driving a 4×2 array of Samsung QM43C signage and QM43B-T interactive displays (Floor 6) for live dashboards and camera feeds.



Interactive Collaboration

Yealink A50 collaboration bar with WPP30 wireless presentation and iPad control for one-touch meeting-room operation and content sharing.



Multi-Floor Interactive Panels

10× Samsung QM43B-T interactive displays on Floor 8, each PC-driven and tied into its own DigiBird video wall controller and iPad control — mirroring the Floor 6 build for flexible, touch-enabled spaces.



Expandable Signage (Optional)

6× Samsung QMC65 65" professional displays for Floor 9, each driven by a dedicated signage PC with wireless HDMI transmission — built for future scale-out.

The proposed solution incorporates enterprise-grade technologies from **Samsung, DigiBird, Yealink, ATEN, LinkAura, VSYS, Apple and OREI** to ensure reliable operation, simplified content management, and a consistent user experience across floors.

DELIVERY

Scope of Work

The scope of work includes the complete execution of the signage, interactive display and collaboration system as detailed in the Bill of Materials. Four key work streams are covered end-to-end.



Supply of Equipment

Samsung QM43C / QM43B-T / QMC65 displays, DigiBird video wall controller, Yealink A50 collaboration bar & WPP30 wireless presentation, Apple iPad control, ATEN KVM switch & USB extenders, LinkAura fiber HDMI cabling, VSYS floor stands / scissor mounts, and optional Floor 9 PCs, wireless transmitters, video matrix and UPS backup.



Installation Works (Floor 6)

Mounting of the 8-panel signage/interactive array on VSYS floor stands, installation of the Yealink collaboration bar and TV mount, structured HDMI/USB/control cabling including steel pipe structure and data socket termination, and cable management.



Display & Video Wall Integration

Configuration of the DigiBird video wall controller for the 4x2 signage/interactive array, source routing across 8x HDMI inputs, EDID/HDCP handling, and content layout calibration for dashboards and live feeds.



Collaboration & Distribution

Yealink A50 conferencing setup, WPP30 wireless screen-share pairing, iPad control configuration, ATEN CS724KM KM switch integration, and LinkAura hybrid fiber AOC HDMI cabling for long-run 4K@60Hz transport.

QUALITY

Control, Testing & Documentation

Control & Automation

iPad-based control for the Floor 6 collaboration room, ATEN CS724KM KM switch for shared keyboard/mouse control across sources, and an intuitive day-to-day workflow for simple, reliable use.

Testing & Commissioning

Full functional testing of all display and collaboration systems, signal verification across HDMI/USB links, video wall layout and EDID/HDCP validation, and end-user testing.

SYSTEM DESIGN

Solution Architecture

The signage and collaboration system is built on a layered architecture spanning display, video wall processing, collaboration and control — centered on the Floor 6 signage and collaboration core, with Floors 8 and 9 extending the same display standard as parallel networks.

**Display**

Samsung QM43C, QM43B-T, QMC65

**Video Wall**

DigiBird 8×8 Controller, VSYS Mounts

**Collaboration**

Yealink A50, WPP30 Wireless

**Distribution**

LinkAura Fiber HDMI, ATEN Matrix (F9)

**Control**Apple iPad, ATEN CS724KM KM
Switch**Network**Client LAN/PoE, ATEN UCE60 USB-
Cat5**Signage & Collaboration Core — Floors 6 & 8**

Floor 6 and Floor 8 each run their own DigiBird video wall controller, PC-driven displays and iPad control point, with Floor 6 additionally hosting the Yealink collaboration bar. Floor 9 extends the same Samsung display standard as an optional, future-ready network.

BRANDS

Key Technology Partners

DISPLAY

Samsung

QM43C signage, QM43B-T interactive touch panel, QMC65 65" professional display.

VIDEO WALL

DigiBird

8×HDMI-in / 8×HDMI-out video wall controller with built-in preview, 1U.

COLLAB

Yealink

A50 collaboration bar, WPP30 wireless presentation, dedicated TV mount.

CONTROL

ATEN

CS724KM KM switch, UCE60 USB extenders, 8×8 video matrix (Floor 9 optional).

BILL OF MATERIALS

Floor 6 — Video Wall & Collaboration Room

Includes installation, testing and commissioning.

#	Brand	Model	Description	Qty
1	Samsung	QM43C	43" Signage Display	4
2	Samsung	QM43B-T	43" Interactive Display Panel	4
3	VSYS	VTLX16-69FW	Scissor Wall Mount Bracket	8
4	Dell	QCS1250	Dell Pro Slim SFF QCS1250 — i7-14700, 32GB RAM, 1TB SSD, Win11 Pro 3-Year, PNY RTX A400 4GB DDR6 GPU	4
5	DigiBird	DB-VWC2-B8H8H-PV	B-Series 8× HDMI input, 8× HDMI output video wall controller, with built-in preview, 1U	1
6	Yealink	A50-010	Leading Platform Collaboration Bar for medium to large rooms	1
7	Yealink	VB-TVMount-01	TV Mount for A50 Main / A25/A40/S40	1
8	Yealink	WPP30	Wireless Presentation Pod	1
9	Apple	iPad	10.7" Wireless iPad — Control Interface	1
10	ATEN	CS724KM-AT	4-Port USB KM Switch	1
11	ATEN	UCE60-AT	USB Cat 5 Extender	4
12	LinkAura	LA-AOC-4KHD2-15	HDMI 2.0 D-D Hybrid Fiber Active Optical Cable, two detachable connectors, 4K@60Hz, 18Gbps, YUV4:4:4, EDID/HDCP2.2/HDR/ARC, 15m	8
13	ATEN	2L-7D02H-1	2m HDMI 19M-HD19M Gold-UL20276 Cable, V2.0	4
14	Sysconic	Service	Installation, Testing and Commissioning — includes steel pipe structure	1

BILL OF MATERIALS

Floor 8

FLOOR 8

Interactive display deployment with dedicated video wall control — supply scope.

#	Brand	Model	Description	Qty
1	Samsung	QM43B-T	43" Interactive Display Panel	10
2	VSYS	VTLX16-69FW	Scissor Wall Mount Bracket	10
3	Dell	QCS1250	Dell Pro Slim SFF QCS1250 — i7-14700, 32GB RAM, 1TB SSD, Win11 Pro 3-Year, PNY RTX A400 4GB DDR6 GPU	10
4	DigiBird	DB-VWC2-B8H8H-PV	B-Series 8× HDMI input, 8× HDMI output video wall controller, with built-in preview, 1U	1
5	Apple	iPad	10.7" Wireless iPad — Control Interface	1
6	ATEN	CS724KM-AT	4-Port USB KM Switch	1
7	ATEN	UCE60-AT	USB Cat 5 Extender	10
8	LinkAura	LA-AOC-4KHD2-15	HDMI 2.0 D-D Hybrid Fiber Active Optical Cable, two detachable connectors, 4K@60Hz, 18Gbps, YUV4:4:4, EDID/HDCP2.2/HDR/ARC, 15m	10
9	ATEN	2L-7D02H-1	2m HDMI 19M-HD19M Gold-UL20276 Cable, V2.0	4

BILL OF MATERIALS

Floor 9 — Optional

FLOOR 9 — OPTIONAL SCOPE

Professional display expansion — supply scope, for future rollout.

#	Brand	Model	Description	Qty
1	Samsung	QMC65	65" Professional Display Panel	6
2	VSYS	VTLX16-69FW	Scissor Wall Mount Bracket	6
3	Dell	QCS1250	Dell Pro Slim SFF QCS1250 — i7-14700, 32GB RAM, 1TB SSD, Win11 Pro 3-Year, PNY RTX A400 4GB DDR6 GPU	2
4	OREI	WHUD3-165-K	Wireless HDMI Transmitter / Receiver	8

FLOOR 9 — OPTIONAL ITEMS

Extended rack and redundancy items — supply scope.

#	Brand	Model	Description	Qty
1	Generic	AV Rack	27" Floor Mount AV Rack	1
2	DigiBird	DB-VWC2-B8H8H-PV	B-Series 8× HDMI input, 8× HDMI output video wall controller, with built-in preview, 1U	1
3	Apple	iPad	11" Apple iPad	1
4	OREI	WHUD3-165-K	Wireless HDMI Transmitter / Receiver	8
5	Dell	QCS1250	Dell Pro Slim SFF QCS1250 — i7-14700, 32GB RAM, 1TB SSD, Win11 Pro 3-Year, PNY RTX A400 4GB DDR6 GPU	2
6	Quant	SMT-R003-I	30-Minute Backup UPS	1

REFERENCE

Site Overview

Reference collaboration / video-wall room, used as the design basis for the Floor 6 signage and video wall deployment.



4×2 wall-mounted display array (live camera feeds on top row, dashboard content on bottom row) above a boardroom-style conferencing table with in-table power/data connectivity — the intended Floor 6 signage and video wall experience.

ROLLOUT PLAN

Mobilization Plan

Upon receipt of an approved purchase order and project confirmation, mobilization activities will be initiated across four structured phases.

1

Project Initiation

- Kick-off meeting with client stakeholders
- Site verification per floor (6, 8, 9)
- Finalization of equipment layout and integration requirements

2

Resource Deployment

- AV engineers
- Installation technicians (Floor 6)
- Commissioning specialists

3

Material Mobilization

- Procurement and delivery coordination
- Logistics planning across floors
- Equipment staging and pre-configuration

4

Site Preparation

- Coordination with site contractor and IT team
- Verification of power and network readiness per floor
- Installation scheduling and access/elevator coordination

ASSURANCE

Warranty, Support & General Notes

Warranty Coverage — 3 Years

All supplied equipment shall carry manufacturer standard warranty against manufacturing defects, or as per OEM standard warranty policy.

Support During Warranty

- Remote technical support
- Troubleshooting assistance
- Configuration support
- Fault diagnosis
- On-site support visits for critical system issues
- Replacement coordination for defective hardware

Mishandling / misuse

Physical damage caused by mishandling, misuse, or unauthorized modification of any supplied equipment.

Environmental

Power abnormalities, environmental damage, or conditions outside the specified operating environment.

Third-party scope

Third-party system failures or issues originating outside the supplied scope of work.

FINE PRINT

General Notes

- Items and quantities are as per the client's requirement (Etihad Rail).
- Floor 6 scope includes installation, testing and commissioning; Floor 8 and Floor 9 are currently supply-only scope — installation to be quoted separately if required.
- Floor 8 now mirrors the Floor 6 equipment build (video wall controller, PC-driven displays, iPad control) but remains a supply-only line item pending a separate installation quote.
- Floor 9 is an optional/alternate scope for future expansion, not part of the core Floor 6/8 deployment.
- Power and network connections to be provided by the client at each floor.
- Civil works, including digging and tile removal (if needed), fall within the client's scope.
- Delivery: 3–4 days from order confirmation, per current material lead times.
- Any addition or change to the Bill of Materials, scope of work, or this specification will require a revised document.
- Document validity: 30 days from date of issue.